

RVSS – REQUIRED EROSION AND SEDIMENT CONTROL PLAN (ESCP) NOTES

- 1. 1200-C/CN Permit Applicability:** For sites covered under the 1200-C/CN permit, the permit registrant is responsible for meeting all conditions of the 1200-C/CN permit. This ESCP has been developed to facilitate compliance with the 1200-C/CN permit. In cases of discrepancies or omissions, the 1200-C/CN permit requirements supersede the requirements of this plan. The permit registrant is required to alter the ESCP depending on site conditions to be protective of water quality.
- 2. Minimum Requirements and Prohibited Discharges:** The ESCP is the minimum effort required to prevent prohibited discharges and must be updated as site conditions change. Prohibited discharges include the following:
 - a. Visually turbid or sediment-laden water;
 - b. Concrete and concrete wastewater;
 - c. Wastewater from washing and cleanout of stucco, paint, form release oils, curing compounds, and other construction materials;
 - d. Fuels, oils, or other pollutants used in vehicle and equipment operation and maintenance;
 - e. Soaps, solvents, or detergents used to wash vehicles, equipment, sanitary facilities, etc.;
 - f. Wheel/tire wash wastewater;
 - g. Hydro-demolition water and saw-cutting slurry; and
 - h. Toxics or hazardous substances from a spill or other release.
- 3. Plan Availability:** The ESCP must accurately reflect current site conditions, be kept on site, and be available for review by the permitting authority, DEQ, or the local municipality.
- 4. Implementation and Maintenance:** All components of the approved ESCP must be installed, implemented, and maintained, and temporary ESC measures must remain until permanent stabilization is achieved.
- 5. Pre-Construction Meeting:** A pre-construction meeting is required to verify proper BMP installation before construction begins; all BMPs must be installed prior to scheduling, and no ground-disturbing work may occur until approved by RVSS (schedule at 541-664-6300).
- 6. Natural Buffer Zone:** Maintain and clearly delineate any existing natural buffer within 50 feet of waters of the state.
- 7. Sediment Control:** Provide sediment control along the site perimeter and at all storm drain inlets at all times, both within the site and at the boundary.
- 8. Flow and Volume Control:** Control peak flow rates and total stormwater volume to minimize erosion at discharge points and in downstream channels and streambanks.
- 9. Clearing and Grading Sequencing:** Sequence clearing and grading to minimize inactive exposed soils that may erode.
- 10. Track-out Prevention:** Prevent sediment tracking onto roads using BMPs such as a stabilized construction entrance, graveled/paved exits and parking, graveling unpaved on-site roads, or a tire wash; these must be in place before land-disturbing activities.
- 11. Material and Waste Management:** Establish material and waste storage areas and non-stormwater controls to prevent prohibited discharges, including concrete washout, wash water from stucco/paint/curing compounds, and vehicle/equipment fueling, maintenance, and storage.
- 12. Concrete Washout:** Install concrete truck and equipment washout areas before beginning concrete work.
- 13. Temporary Stabilization:** Provide temporary stabilization for any area where work ceases for 14 days or more, and stabilize soils before weekends/holidays as needed. The registrant is responsible for ensuring that soils are stable during rain events at all times of the year.
- 14. Dewatering:** Provide a dewatering plan for all dewatering operations, including removal of accumulated stormwater and uncontaminated groundwater; discharging turbid or sediment-laden water to the storm system is prohibited.
- 15. Engineered Soils:** If engineered soils are used on site, a sedimentation basin/impoundment must be installed to capture all runoff from the engineered soils.
- 16. BMP Inspection and Maintenance:** Inspect BMPs weekly and before predicted rain events. Conduct needed BMP maintenance as soon as possible and prior to any predicted rain event; remove sediment when it reaches one-third of BMP capacity.
- 17. 1200-C/CN Inspection Requirements:** For 1200-C/CN sites, ESC inspections must be performed by a Designated Erosion and Sediment Control Inspector, and visual monitoring logs and reports must meet DEQ permit requirements.
- 18. Sediment Release Response:** Significant sediment leaving the site must be cleaned up within 24 hours, and the cause must be investigated with corrective actions implemented within the same 24 hours.
- 19. Pollutant Cleanup:** Do not wash sediment or pollutants into storm systems or drainage ways; cleanup must use vacuuming, dry sweeping, or physical pickup.
- 20. Final Stabilization:** Final stabilization must be achieved on all portions of the site to ensure all disturbed areas pose no reasonable potential for discharge from construction-related sediment or turbidity. Acceptable permanent stabilization methods include:
 - Landscaping, vegetation, or mulch providing $\geq 70\%$ cover on all exposed areas.
 - Grading, flattening, or down-cutting pervious (uncompacted) soils to eliminate discharge potential to the storm system or surface waters.
 - Stabilizing slopes steeper than 4H:1V using one of the following:
 - Landscaping, vegetation, or mulch providing $\geq 70\%$ cover; or
 - Hydroseeding with tackifier and biodegradable erosion control matting designed to prevent erosion without active maintenance.
- 21. Removal of Temporary Controls:** After final stabilization, remove and properly dispose of all temporary ESC measures and accumulated sediment.